


- KS1000 AWP / LPCB insulated wall panel horizontally laid
- Internal closure flashing with 100mm overlap
- Site applied LPCB certified PIR insulation board any gaps filled with fire rated canister insulation
- Low profile stitching screws with minimum 14mm diameter non ferrous EPDM backed washer fitted at maximum 450mm centres
- Air seal - 6mm bead of gun grade sealant
- Self-drilling self-tapping primary fixings with minimum 19mm diameter non-ferrous EPDM backed washer at 1000mm centres
- Drip flashing with 100mm sealed overlaps or butt straps
- External closure flashing with 100mm sealed overlaps or butt straps
- Kingspan Multibeam any joints sealed with a film backed butyl tape
- Soffit flashing with 100mm sealed butt straps
- Door track



Note for KS1000WV Profile: 9x6mm PVC foam tape should be used instead of the noted 4mm diameter butyl rubber sealant between the face of the panel and any external flashings including vertical tophat flashings.

Notes:

Rev	Description	Chkd	Date



Insulated Roof
& Wall Panels



TECHNICAL SERVICES

Kingspan Limited
Greenfield Business Park No. 2, Greenfield,
Holywell, Flintshire, CH8 7GJ, UK
www.kingspanpanels.co.uk
t: 0800 587 0090

Carrickmacross Road,
Kingscourt, Co.Cavan, Ireland
www.kingspanpanels.ie
t: 00353 42 96 98529

Client

Project

Drawing

KS1000 AWP Hz
Roller Shutter Door Head

Status

Drawn by	Checked by	Date
RL	JP	11/02/15

Drawing Number	Revision
AWPHz15043	

This drawing is the property of Kingspan and may not be reproduced in any way without written consent from Kingspan.