



Wall Elevation



- Kingspan Horizontal Panel Vertical Support
- Intergrated window unit
- Air seal - EPDM VJ2 bubble gasket 95x10mm
- Site applied LPCB certified PIR insulation board
any gaps filled with fire rated canister insulation
- KS1000 AWP / LPCB insulated wall panel horizontally laid
- Self-drilling self-tapping primary fixings with
minimum 16mm diameter non-ferrous EPDM backed washer
- Air seal gun grade seal to male joint inline with internal air seal
- AWP joint filler bedded on gun grade sealant
- 4mm diameter butyl rubber sealant
- Option A vertical tophat 30mm deep with
100mm sealed butt straps at maximum 6000mm lengths



SECTION D-D

Note for KS1000WV Profile: 9x6mm PVC foam tape should be used instead of the noted 4mm diameter butyl rubber sealant between the face of the panel and any external flashings including vertical tophat flashings.

Notes:

Rev	Description	Chkd	Date



**Insulated Roof
& Wall Panels**

enviro*care*[®]

TECHNICAL SERVICES

Kingspan Limited
Greenfield Business Park No. 2, Greenfield,
Holywell, Flintshire, CH8 7GJ, UK
www.kingspanpanels.co.uk
t: 0800 587 0090

Carrickmacross Road,
Kingscourt, Co.Cavan, Ireland
www.kingspanpanels.ie
t: 00353 42 96 98529

Client

Project

Drawing

KS1000 AWP Hz
Integrated Window Jamb

Status

Drawn by RL	Checked by JP	Date 11/02/15
Drawing Number AWPHz15037		Revision

This drawing is the property of Kingspan and may not be reproduced in any way without written consent from Kingspan.